

Kitchen_7

Level: Level 0 · Internal condition: 1 Bed Apt. Kitchen - Kitchen_7

DESIGN CRITERIA

	Heating	Cooling
Room set point	-50.0 °C	150.0 °C
Outdoor dry bulb	—	—
Outdoor RH (coincident)	—	—

ROOM HUMIDITY

Humidification set point	—
lower RH limit	
Dehumidification set point	—
upper RH limit	

SIZING (TAS DESIGN LOADS)

	Heating	Cooling
Design load	0 W	0 W
Design load per area	0.0 W/m ²	0.0 W/m ²
Sizing multiplier	not set	not set

Design loads: from Tas sizing — date/currency not recorded

HEATING

Design day	Leeds_TRY ANN HTG 100% CONDS DB	
	Design day	Full year
Peak sensible load	1,626 W	920 W
Peak hour	13:00–14:00	1 Jan 00:00–01:00 (HOY 1)
Room dry bulb	14.3 °C	13.7 °C
Room resultant	13.0 °C	13.0 °C
Room RH	22 %	57 %
Room humidity ratio	2.2 g/kg	5.6 g/kg
Outdoor dry bulb	—	3.3 °C
Outdoor RH	—	100 %

SENSIBLE LOAD COMPONENTS AT PEAK

Component	Design day (W)	Full year (W)
Equipment (sensible)	0	50
Infiltration / ventilation	-309	-159
Building heat transfer	-625	-473
External conduction — opaque	-464	-225
External conduction — glazing	-227	-112

Zero at both peaks (not listed): Solar, Lighting, Occupancy (sensible), Air movement (inter-zone), Air handling unit, Occupancy (latent), Equipment (latent)
 Components as the simulation reports them at each peak hour: + gain to the room air, – loss from it. No total is derived.

COOLING

Design day	Leeds_TRY ANN CLG 0% CONDS DB=>GRad	
	Design day	Full year
Peak sensible load	1,307 W	1,246 W
Peak hour	00:00–01:00	2 Aug 04:00–05:00 (HOY 5117)
Room dry bulb	20.1 °C	17.3 °C
Room resultant	21.4 °C	18.5 °C
Room RH	88 %	98 %
Room humidity ratio	13.0 g/kg	12.2 g/kg
Outdoor dry bulb	—	15.2 °C
Outdoor RH	—	94 %

SENSIBLE LOAD COMPONENTS AT PEAK

Component	Design day (W)	Full year (W)
Solar	0	11
Equipment (sensible)	50	50
Infiltration / ventilation	-14	-32
Building heat transfer	898	946
External conduction — opaque	416	333
External conduction — glazing	-42	-62

Zero at both peaks (not listed): Lighting, Occupancy (sensible), Air movement (inter-zone), Air handling unit, Occupancy (latent), Equipment (latent)
Components as the simulation reports them at each peak hour: + gain to the room air, – loss from it. No total is derived.

RESULTS

	Heating	Cooling
Status	Available	Available
Result source	SAM.Analytical.Tas	SAM.Analytical.Tas
Read into model	27 Sep 2026 20:42	27 Sep 2026 20:42
Matches current model	not recorded	not recorded

Peak hour: a design-day peak has an hour of the day only, no date; a full-year peak shows day and hour, no year, and its hour of the year (HOY 1 = 1 Jan 00:00–01:00, HOY 8760 = 31 Dec 23:00–24:00).
Design loads (sizing) and simulated peaks are shown side by side for information; no acceptance rule is applied.